

1 **A simple approach to multi degree-of-freedom loading in a geotechnical centrifuge**

2 Manuscript accepted to *ASTM Geotechnical Testing Journal* on 11/07/2018

3 **Conleth D. O'LOUGHLIN**

4 Centre for Offshore Foundation Systems – M053,

5 A node of ARC Centre for Geotechnical Science and Engineering

6 University of Western Australia

7 35 Stirling Highway, Crawley, Perth, WA 6009, Australia

8 Tel: +61 8 64887326

9 Email: [conleth.oloughlin@uwa.edu.au](mailto:conleth.oloughlin@uwa.edu.au)

10 **Michael L. COCJIN**

11 Centre for Offshore Foundation Systems

12 A node of ARC Centre for Geotechnical Science and Engineering

13 Email: [michael.cocjin@research.uwa.edu.au](mailto:michael.cocjin@research.uwa.edu.au)

14 **Susan M. GOURVENEK**

15 Centre for Offshore Foundation Systems, UWA

16 A node of the ARC Centre for Geotechnical Science and Engineering

17 Email: [susan.gourvenec@uwa.edu.au](mailto:susan.gourvenec@uwa.edu.au)

18 Sam A. STANIER

19 Centre for Offshore Foundation Systems, UWA

20 A node of the ARC Centre for Geotechnical Science and Engineering

21 Email: [sam.stanier@uwa.edu.au](mailto:sam.stanier@uwa.edu.au)

22

23 No. of words: **4,102** (excluding ABSTRACT, including Sections 1 – 6)

24 No. of tables: **0**

25 No. of figures: **11**

## 26 **ABSTRACT**

27 This paper considers an alternative approach for multi-planar loading and multi degree-of-freedom movement in  
28 geotechnical centrifuge model tests. The multi degree-of-freedom loading system allows for vertical load  
29 control on the vertical axis, and either displacement or load control on the two horizontal axes, whilst allowing  
30 rotation about these axes. The system is described in detail and the system performance is validated through  
31 results from a centrifuge test comparing observed results with analytical and numerical solutions. The validation  
32 of the system considers a mudmat foundation under large amplitude lateral displacement, where two  
33 displacement degrees-of-freedom and two rotational degrees-of-freedom were of interest. However, the  
34 apparatus is versatile and can be used for testing other foundation types or pipelines, with up to six degrees-of-  
35 freedom.

## 36 **1. INTRODUCTION**

37 Offshore structures are typically subjected to multi-directional loading and respond with displacement in  
38 multiple degrees of freedom. Foundations of fixed-base structures, oil and gas platforms or wind turbines,  
39 experience a combination of vertical load from the self-weight of the structure, horizontal loads from the action  
40 of wind, waves and currents, and moment loading from the height offset between the action of the horizontal  
41 loads and the foundation; foundations of subsea structures can experience complex multi-directional loading  
42 from multiple pipeline and spool expansion loads acting at vertical and horizontal eccentricities to the centroid  
43 of the foundation (Randolph 2012, Feng et al. 2014); offshore pipelines are subject to vertical self-weight loads,  
44 multi-directional installation loads and thermally induced axial and lateral loads during operation and respond  
45 with settlement/burial, axial walking and lateral buckling.

46 Independent control of loading and acquisition of displacement, or vice versa, in all six degrees of freedom  
47 poses quite an experimental challenge for actuation systems. This is more achievable at  $1g$  than in a centrifuge  
48 as the space requirements for the actuation and position measurement systems can be more easily  
49 accommodated on the laboratory floor than within the constrained space available on a centrifuge package  
50 (Byrne 2014). Centrifuge actuators typically have two or three displacement degrees of freedom (DoF) along the  
51 horizontal and vertical planes, although actuation systems that add a rotational DoF have also been developed  
52 (Dean et al. 1997, Punrattanasin et al., 2003, Cocjin and Kusakabe 2013, Kong 2012, Zhang et al. 2013,  
53 Gaudicheau et al. 2014). To the authors' knowledge a six DoF actuation system has not yet been developed for  
54 use in a geotechnical centrifuge.

55 Independent control of loads or displacement in all degrees of freedom is not a necessity for many practical  
56 applications involving multi-directional loading and resulting displacements. A practical approach to multi DoF  
57 actuation in a geotechnical centrifuge may, in many cases, be to use existing actuators to control displacements  
58 or loads along the principal axes, whilst permitting rotational degrees of freedom about the same axes. This  
59 paper describes such an approach, firstly describing a new multi-DoF loading system, before assessing the  
60 system performance as measured in a centrifuge mudmat test on normally consolidated kaolin clay.

## 61 2. DESIGN OF THE MULTI-DoF LOADING SYSTEM

### 62 2.1 General arrangement

63 The general arrangement of the new multi-DoF loading system, actuator and model is illustrated in **Figure 1**.

64 The multi-DOF loading system (item <sup>[1]</sup> in **Figure 1**) enables movement in four DoF under vertical load control  
65 and with either horizontal load or displacement control. As shown by **Figures 1(a-b)**, it is designed to be  
66 operated in conjunction with an actuator<sup>[2]</sup> that provides motion in the vertical and horizontal directions. The  
67 actuator is mounted on top of a strongbox containing the soil model. The main part of the multi-DoF loading  
68 system is a “C-shaped loading arm” (described in detail in the following section) that connects to the actuator by  
69 way of a solid aluminium shaft secured at the collar connection<sup>[6]</sup> of the actuator’s vertical axis. Two rotational  
70 DoF are allowed for within the C-shaped loading arm, which together with the two translational DoF provided  
71 by the horizontal and vertical axes of the actuator, comprise the four DoF allowed on the model infrastructure.  
72 This is shown by **Figure 2**, which also defines the positive sign convention for the loads and displacements, and  
73 the reference point (RP) where the loads and displacements are defined on a rectangular foundation.

74 The multi-DoF loading system was developed for and trialled on a model pipeline end termination mudmat,  
75 where displacement along the longitudinal and vertical axes, and rotation about the two orthogonal horizontal  
76 axes were of interest (i.e. four DoF). However, the use of an actuator with a second horizontal axis and an  
77 additional rotational degree of freedom within the C-shaped arm would enable load or displacement control in  
78 three DoF and movement in all six DoF (without control in the rotational DoF).

79 The multi-DoF loading system can be operated in either load or displacement control on the horizontal axis and  
80 on load control on the vertical axis. Motion along these actuator axes is provided by DC servo-motors that drive  
81 vertical and horizontal lead screws<sup>[7,8]</sup> (**Figure 1(b)**). The actuator axes are controlled by the UWA Package  
82 Actuator Control System (PACS) (De Catania et al., 2010), an in-house software written in Labview. This

83 software runs on an in-flight computer mounted on the centrifuge and acts as a slave to a master computer in the  
84 centrifuge control room, with communication via an Ethernet link across an optical slip ring. The control  
85 software is operated via a remote desktop linked to the in-flight computer.

86 Load- or displacement-controlled operation of the actuator can be achieved with a software feedback loop using  
87 the outputs of a load cell<sup>[11,12]</sup> or a displacement transducer<sup>[4,5]</sup>. The software can also automate loading or  
88 displacement sequences through its waveform generator. The waveform can be generated for monotonic loading  
89 or displacement sequences using a ramp function, or cyclic loading or displacement sequences using a sine,  
90 square, triangle or sawtooth function (De Catania et al. 2010).

### 91 *2.2 Loading arm description*

92 As described above, the C-shaped loading arm provides the rotational DoF. Details of the loading arm are  
93 provided in **Figures 1(c-d)**. The upper C section is fabricated from aluminium and is 235 mm long along the  $y$   
94 axis, with provision for a bolted connection to the aluminium shaft attached to the actuator. An eyelet<sup>[17]</sup> is  
95 provided at the free end of the upper C section to append the vertically-suspended load cell<sup>[11]</sup>, whilst the other  
96 end is bolted to a vertical shaft forming the middle C section. The shaft for the middle C section is fabricated  
97 from stainless steel, 105 mm long with 25 mm diameter, and is attached to the lower C section by a hinge. The  
98 lower C section is comprised of an S-shaped load cell<sup>[12]</sup>, an in-line stainless steel cylindrical roller bearing<sup>[14]</sup>  
99 and a 100 mm long aluminium section with a hinge<sup>[15]</sup> at its free end. The roller bearing provides the rotational  
100 DoF about the  $y$  axis, whereas the hinge at the end of the aluminium section provides the connection to the  
101 foundation model and the rotational DoF about the  $x$  axis. An eyelet<sup>[16]</sup>, located directly above this hinge,  
102 connects to the vertically-suspended load cell<sup>[11]</sup> via wire cable and polyethylene line (to eliminate rigidity),  
103 completing the connection between the upper and lower C sections. The height of the hinge<sup>[15]</sup> from the base of  
104 the attached model foundation is adjustable depending on the test requirements.

### 105 *2.3 System instrumentation*

106 A vertically-suspended load cell<sup>[11]</sup> with a measurement range of 1.4 kN is suspended in-line between the  
107 eyelets<sup>[17,16]</sup> on the upper and lower C sections. The load cell was connected to the upper eyelet<sup>[17]</sup> using steel  
108 cable, but to the lower eyelet<sup>[16]</sup> using the polyethylene line, to ensure that the link between the two eyelets  
109 could only be in tension. This was a design requirement as this load cell measures the combined self-weight of  
110 the lower C section and the attached model foundation when not in contact with the soil surface. The submerged  
111 weight of the foundation,  $V$ , and hence the on-bottom pressure applied to the soil, can then be controlled by

112 operating the vertical axis of the actuator under load control using the analogue feedback from the vertical load  
113 cell. The S-shaped axial load cell<sup>[12]</sup> on the lower C section has a measurement range of 150 N and measures the  
114 horizontal load,  $H$ , along the  $y$  axis.

115 Displacements along the  $y$  and  $z$  axes are measured using the optical encoders located on the vertical and  
116 horizontal axes of the actuator. A laser displacement sensor<sup>[5]</sup> (Keyence®, model LB-70-11) with a  
117 measurement range of 80 mm is located on a bracket connected to the actuator and oriented towards a target<sup>[18]</sup>  
118 at the junction of the middle and lower C sections of the loading arm (**Figure 1(c)**). This provides an additional  
119 measurement of the foundation displacement along the  $y$  axis, independent of that determined from the optical  
120 encoder on the actuator's horizontal axis.

121 Four additional laser displacement sensors<sup>[4]</sup> with a measurement range of 80 mm measure the vertical  
122 displacement at each corner of the foundation, although these measurement locations can be adjusted if required.  
123 These displacement sensors are mounted directly above the model foundation on a steel plate that is fixed to the  
124 actuator, such that the sensors move horizontally in unison with the actuator and hence the model foundation  
125 (**Figure 1(b)**). Independent measurement of these corner vertical displacements allows the rotation about the  $x$   
126 and  $y$  axes –  $\theta_{xx}$  and  $\theta_{yy}$  respectively – to be determined.

### 127 **3. SUMMARY OF CENTRIFUGE TEST USED TO ILLUSTRATE LOADING SYSTEM CAPABILITY**

128 System performance of the multi-DoF loading system is assessed in the next section using the results from a  
129 centrifuge test that was conducted to investigate the load and displacement response of a pipeline end  
130 termination mudmat foundation on normally consolidated clay when subjected to cycles of large-amplitude  
131 lateral movements under low vertical load, simulating the expansion associated with start-up and shut-down  
132 operations of an offshore pipeline. Testing was conducted in the UWA beam centrifuge. A complete description  
133 of this centrifuge, as commissioned in 1989, is provided by Randolph et al. (1991). The centrifuge test results  
134 are reported in model scale, unless stated otherwise, in order to demonstrate the accuracy of the new loading  
135 system.

#### 136 *3.1 Soil model*

137 A normally consolidated kaolin clay sample was prepared from slurry at twice the liquid limit and consolidated  
138 under self-weight in the centrifuge at 100g for 3.5 days. After consolidation was essentially complete, the  
139 centrifuge was stopped and a minimum amount of clay was scraped from the sample to create a level surface.

140 The final sample dimensions were 650 mm by 390 mm in plan with a height of 130 mm. A miniature T-bar  
141 penetrometer (Stewart & Randolph, 1991) with a projected (penetrating) area of 100 mm<sup>2</sup> was used to determine  
142 the depth profile of undrained shear strength,  $s_u$ . The T-bar was penetrated into the soil at a rate of 1 mm/s to  
143 ensure undrained conditions (Randolph & Hope, 2004) and  $s_u$  was determined from the measured penetration  
144 resistance using a constant T-bar factor of 10.5 (Martin & Randolph, 2006). **Figure 3** shows the  $s_u$  profile with  
145 depth, which can be well described by  $s_u = 0.53 + 0.86z$  (kPa), where  $z$  is the penetration depth in prototype  
146 scale (m). The average effective unit weight of the soil,  $\gamma'_{avg} = 5.7$  kN/m<sup>3</sup> was assessed from moisture content  
147 measurements made on a core sample taken after testing, giving a normally consolidated strength ratio of  
148  $(s_u/\sigma'_{vo})_{NC} \sim 0.15$ , similar to that determined from other recent centrifuge studies on UWA kaolin (Chow et al.  
149 2014; Hu et al. 2014; Morton et al. 2014).

### 150 3.2 Model foundation

151 A rectangular mudmat foundation, with aspect ratio  $B/L = 0.5$ , was used in the centrifuge test. **Figure 4** shows a  
152 schematic of this model foundation attached to the loading arm, showing profile views in (a)  $y$ - $z$ , and (b)  $x$ - $z$   
153 planes. The foundation has underside base plate dimensions,  $B = 50$  mm and  $L = 100$  mm (giving a basal area of  
154  $A = 5000$  mm<sup>2</sup>), and a height of 5 mm (equivalent to prototype plan dimensions of 5 m by 10 m and height of  
155 0.5 m). The model foundation was fabricated with an edge 'ski' (inclined at 30°) along each side. The purpose  
156 of the ski was to reduce foundation tipping (overturning) and encourage sliding.

157 The mudmat was fabricated from acetal (polyoxymethylene (POM)) that has a density of 1410 kg/m<sup>3</sup>, which is  
158 sufficiently low to allow a model mudmat of solid section to replicate the self-weight of a field mudmat,  
159 typically manufactured from steel but not solid in section. With the current modelling approach, as described  
160 earlier, adjustment to a targeted submerged on-bottom weight is achieved using load control on the vertical axis  
161 of the actuator. This capability means that scaling of the submerged weight of the prototype foundation is not a  
162 modelling requirement, although was achieved in this case. Acetal has a Young's modulus and Poisson ratio of  
163 3.1 GPa and 0.39 respectively, sufficiently stiff to be considered as rigid relative to the soft clay. Fine silica sand  
164 was glued to the base plate as a rough foundation–soil interface was of interest for these tests. The faces of the  
165 edge 'ski' retained a smooth finish.

166 Circular discs propped on slender posts were located at each corner of the model foundation to serve as targets  
167 for the vertically-orientated laser displacement sensors. The height of the posts can be adjusted to keep the  
168 circular discs above the water surface during the test to avoid refraction of the laser beam in the water.

169 **Figure 5** shows the DoF for the model foundation with the currently configured loading system and the two-  
170 directional actuator. Vertical displacement of the model foundation along the  $z$  axis is quantified either through  
171 the displacement of the actuator's vertical axis,  $w_{(encoder)}$  or through the average of the corner vertical laser  
172 displacements,  $w_{(laser)}$  (**Figure 5(a)**). Horizontal displacement of the model foundation along the  $y$  axis may be  
173 taken either as the displacement of the actuator's horizontal axis,  $u_{y(encoder)}$  or from the independent laser  
174 displacement sensor measurement,  $u_{y(laser)}$  (**Figure 5(b)**). Rotation of the model foundation about the  $x$  and  $y$   
175 axes –  $\theta_{xx}$  and  $\theta_{yy}$  respectively – may be quantified from the difference of corner vertical laser displacement  
176 measurements (**Figures 5(c-d)**). Whilst the current system configuration enables foundation displacement in  
177 four DoF, displacement-control is limited to horizontal  $y$  axis.

### 178 *3.3 Loading program*

179 As described earlier, the four DoF loading system is operated with the vertical axis of the actuator under load  
180 control and the horizontal axis of the actuator under either displacement or load control. The test presented here  
181 to illustrate the performance of the apparatus employed displacement control for the horizontal axis. The time  
182 history of imposed loads and displacements are shown in **Figure 6**: vertical load,  $V$  (**Figure 6(a)**) and horizontal  
183 displacement,  $u_y$  (**Figure 6(b)**).

184 Phase 1 of the test involved foundation touchdown and consolidation under the operative vertical load,  $V_{op}$ .  
185 Foundation touchdown can be performed under either displacement or load control. In this test, displacement  
186 control was used with the vertical axis of the actuator displaced positively – initially at a velocity of 0.1 mm/s,  
187 reducing to 0.01 mm/s as the foundation approached the mudline – until about one third of the targeted load was  
188 observed, at which point the vertical axis of the actuator was switched into load-control mode and a target load  
189 of  $V_{op}$  specified. This process was automated using the PACS software, with manual fine adjustment of the load  
190 control as required. A consolidation period of approximately 4 hours (4.5 years in prototype scale) was allowed  
191 after touchdown of the mudmat to bring the soil beneath the foundation sufficiently close to a fully consolidated  
192 state at the end of the installation phase. During Phase 1 (including the consolidation stage), settlement along the  
193  $z$  axis, and rotation about the  $x$  and  $y$  axes were permitted, but horizontal displacement along the  $y$  axis was not  
194 allowed.

195 Phase 2 involved undrained large amplitude cyclic sliding of the mudmat foundation. As in Phase 1, the actuator  
196 motion was automated using the waveform generator in the PACS software. The sliding cycles are as defined in  
197 **Figure 6(b)** and comprise a forward slide equal to half the breadth of the foundation  $u_{y(max)} = 0.5B$ , a long

198 interim pause during which  $\Delta u_y = 0$ , a backward slide until  $u_y = 0$ , and finally a short interim pause during which  
199  $\Delta u_y = 0$ . The horizontal displacement was carried out at a velocity of 1.0 mm/s. This gives a one-way sliding  
200 duration of 25 s ( $< 3$  days in prototype scale), sufficiently short for any significant dissipation of excess pore  
201 water in the soil beneath the foundation to occur during sliding (Cocjin et al. 2014). The test involved  $N = 40$   
202 loading cycles, with each loading cycle comprising a forward slide, long period of consolidation, backward slide  
203 and short period of consolidation. The long interim pause permitted after each forward slide represents the  
204 period when a pipeline is in operation between scheduled shutdowns, with shutdowns typically occurring a few  
205 times a year. As such the reconsolidation episode at  $u_y = u_{y(max)}$  was 13 minutes, equivalent to 3 months in  
206 prototype scale. The short interim pause permitted after each backward slide simulates the brief shutdown  
207 period after the pipe cools and contracts and the foundation has returned to its installation position,  $u_y = 0$ .  
208 Shutdowns are typically less than a day, modelled in the centrifuge test as 8 s. During Phase 2, settlement along  
209 the  $z$  axis, and rotation about the  $x$  and  $y$  axes were permitted, with horizontal displacement along the  $y$  axis  
210 allowed only during the forward and backward slides but locked during the interim pauses.

211 An operative vertical load,  $V_{op}$  corresponding to  $\sim 30\%$  of the unconsolidated, undrained vertical capacity of the  
212 mudmat foundation, was selected as a realistic field value, and to allow for a pure sliding mechanism in  
213 response to horizontal loading under undrained conditions (Green, 1954; Gourvenec & Randolph, 2003; Cathie  
214 *et al.*, 2008).

#### 215 4. TECHNICAL PERFORMANCE OF THE MULTI-DOF LOADING SYSTEM

216 The technical performance of the multi DoF loading system is examined in this section by considering the load  
217 and displacement response of the model foundation during the test. **Figure 7** shows a time history of the vertical  
218 load,  $V$ ; horizontal displacement,  $u_{y(encoder)}$  (i.e. taken as the horizontal displacement of the actuator); horizontal  
219 load,  $H$ ; vertical displacement,  $w_{(laser)}$  (i.e. taken as the average of the vertical displacements at the foundation  
220 corners ); and foundation rotation about the  $x$  and  $y$  axes –  $\theta_{xx}$  and  $\theta_{yy}$  respectively. The data are provided in  
221 **Figure 7(a)** through to **Figure 7(e)** for vertical touchdown of the foundation, **Figure 7(f)** through to **Figure 7(j)**  
222 for post-installation consolidation and the first 15 undrained sliding cycles, and **Figure 7(k)** through to **Figure**  
223 **7(o)** for the first sliding and re-consolidation cycle.

224 It is clear from **Figure 7** that the system is capable of enabling and measuring required foundation movements  
225 in four DoF; displacements develop along the  $y$  and  $z$  axes, and rotations develop about the  $x$  and  $y$  axes.



226 Displacement along the  $z$  axis,  $w_{(laser)}$ , is continuous during the test as this axis is operated in load control,  
227 whereas displacement only occurs along the  $y$  axis,  $u_{y(encoder)}$  during the forward and backward slides. The  
228 change in  $z$  axis displacement, i.e. settlement,  $\Delta w$ , is positive during the post-touchdown consolidation, cycles of  
229 re-consolidation and during forward slides, but negative during backward slides. As the foundation is free to  
230 rotate about the  $x$  and  $y$  axes,  $\theta_{xx}$  and  $\theta_{yy}$  are non-zero throughout the test, and change most rapidly during the  
231 undrained sliding cycles.

232 Vertical load develops from time,  $t = -240$  s to  $t = 0$  as the foundation is gradually lowered to the soil surface  
233 under displacement control, initially at a displacement rate of 0.1 mm/s (to  $t = -167$  s) and then 0.01 mm/s. From  
234  $t = 0$  the vertical axis was under load control, with the achieved load in the range  $V_{op} = 10 \pm 0.35$  N during the  
235 consolidation phase when  $\Delta u_y = 0$ , and  $V_{op} = 10 \pm 1.5$  N during the undrained sliding cycles when  $\Delta u_y \neq 0$ . The  
236 higher variation in the achieved load is partly due to the difficulty in selecting PID (proportional–integral–  
237 derivative) controller parameters that work effectively during static and non-static conditions, although  
238 mechanical slack between the leadscrew and the nut on the actuator axes can also deteriorate the quality of the  
239 load control. **Figure 8** shows the equivalent response measured in separate tests in which the actuator axes were  
240 adjusted mechanically to reduce backlash, where the variation in the maintained load during the undrained  
241 sliding cycles is reduced approximately threefold. However, it is worth noting that the maximum variation  
242 corresponds to 0.1 % of the measurement range of the load cell (1.4 kN) and that the variation would reduce if a  
243 load cell with a lower measurement range were used. The horizontal load,  $H$  is essentially zero during  
244 foundation touchdown and post-touchdown consolidation, which is to be expected as  $u_y = 0$  during this time.  
245 During the undrained sliding cycles,  $H$  is positive during forward slides and negative during backward slides.  $H$   
246 also increases with increasing loading cycles, reflecting the higher seabed strength brought about by the  
247 consolidation periods between sliding events.

248 **Figure 9** compares the foundation displacements as assessed from the actuator motion with the independent  
249 laser displacement sensor measurements in: (a) vertical and (b) horizontal directions. The vertical displacement  
250 of the actuator,  $w_{(encoder)}$ , is typically no more than 0.2 mm lower than that determined from the average of the  
251 laser displacement sensors,  $w_{(laser)}$ , equivalent to less than 4% difference in the actual displacement. The  
252 horizontal displacement of the actuator  $u_{y(encoder)}$  is initially close to the value measured by the horizontal laser  
253 displacement sensor,  $u_{y(laser)}$ . However, as the cycles progress, the difference between  $u_{y(encoder)}$  and  $u_{y(laser)}$   
254 increases to a maximum deviation of 1.5 mm (6 %) due to a progressive increase in system compliance brought

255 about by the increasing horizontal load,  $H$ , reflecting the strength increases in the clay. This reduced slide  
 256 displacement was negligible for the current test, involving slide distances of  $0.5B$ . In other scenarios it may be  
 257 more appropriate to use the independent displacement measurement rather than the encoder as the displacement  
 258 feedback for the actuator's horizontal axis.

## 259 5. EXAMPLE APPLICATION OF THE MULTI-DOF LOADING SYSTEM

260 The load and displacement response from the sliding mudmat foundation test is presented in **Figure 10**. **Figure**  
 261 **10(a)** shows (imposed) horizontal displacement against (observed) settlement over the 40 cycles of the test, and  
 262 **Figure 10(b)** shows the cycle-by-cycle increase in horizontal sliding resistance against the (imposed) horizontal  
 263 displacement. **Figures 10(c-d)** represent the measured displacement and load respectively, midway through the  
 264 slide, i.e. at  $u_y/B = 0.125$ . Foundation rotations,  $\theta_{xx}$  and  $\theta_{yy}$  are provided in **Figure 10(e)**, showing that rotations  
 265 are minimal.

266 An independent quantification of the foundation consolidation settlement was made by considering the  
 267 difference in void ratio profiles with depth obtained within the foundation footprint and in free-field soil ( $e_0$ )  
 268 from vertical core soil samples taken after the test (inset **Figure 11(a)**). The final consolidation settlement is  
 269 calculated from the measured change in void ratio by

$$\sum w_{cons.f} = \int_{z=0}^{z \rightarrow \infty} \frac{\Delta e}{1 + e_0} dz \quad (1)$$

270 and is seen to agree well with the final value of consolidation settlement  $\Sigma w_{cons}$  determined from the laser  
 271 displacement sensors as shown in **Figure 11(a)**.

272 The difference between the total observed settlement,  $\Sigma w$  and the accumulated consolidated settlement,  $\Sigma w_{cons}$  is  
 273 a measure of the amount of soil that accumulates as berms on either side of the foundation during the sliding  
 274 cycles, shown in **Figure 11(b)**.

275 The measured horizontal resistance,  $H$ , expressed as a coefficient of sliding friction,  $\mu = H/V$ , during the first  
 276 slide and during the loading cycles is plotted against normalised foundation displacement,  $u_y/B$  in **Figure 12(a)**  
 277 and **Figure 12(b)**, respectively. During the first slide, a peak resistance at low horizontal displacement is  
 278 observed which then reduces with foundation displacement, reaching a steady state of  $\mu = 0.15$  at  $u_y/B \approx 0.15$ .  
 279 The steady state coefficient of sliding friction derived from the test observation agrees well with analytical and  
 280 numerical predictions based on critical state soil mechanics (Cocjin et al. 2016; Feng & Gourvenec 2015).

281 **Figure 12(c)**, which plots the mid-slide values of coefficient of sliding friction,  $\mu$  against cycle number,  $N$   
282 shows that a long term sliding resistance given by  $\tan\phi'$  where  $\phi' = 23.5^\circ$  is the internal angle of soil friction, is  
283 eventually achieved when the soil has undergone sufficient cycles of sliding (and hence shearing), pore pressure  
284 generation and reconsolidation to reach critical state conditions, resulting in no further contraction and excess  
285 pore pressure generation (Cocjin et al. 2015, Cocjin et al. 2016, Feng & Gourvenec 2016).

## 286 **6. CLOSING REMARKS**

287 Multi degree-of-freedom loading in a geotechnical centrifuge environment is challenging, but necessary to  
288 understand the behaviour of geotechnical structures that experience combined loading. This paper has simplified  
289 the challenge somewhat by proposing a multi DoF loading system that uses a conventional two or three  
290 dimensional actuator to actuate along the principal axes, whilst using roller bearings to allow rotation about the  
291 same axes. Whilst the system does not permit for independent control of the rotational DoF, the simplicity and  
292 flexibility of the system is appealing and sufficient for simulating various boundary value problems involving  
293 multi-directional loading and freedom of movement. This has been demonstrated in this paper by simulating the  
294 whole-life cycle of a pipeline end termination mudmat under large amplitude lateral displacement. The loading  
295 arm apparatus could also be used to investigate the performance of other foundation systems or pipelines under  
296 selected modes of multi-directional loading.

## 297 **7. ACKNOWLEDGEMENTS**

298 This work forms part of the activities of the Centre for Offshore Foundation Systems (COFS), currently  
299 supported as a node of the Australian Research Council's Centre of Excellence for Geotechnical Science and  
300 Engineering, and through the Fugro Chair in Geotechnics, the Lloyd's Register Foundation Chair and Centre of  
301 Excellence in Offshore Foundations and the Shell EMI Chair in Offshore Engineering. The work presented in  
302 this paper is supported through ARC grant DP140100684. Development of the multi DoF loading system was  
303 supported through a contract with Fugro AG.

## 304 **8. REFERENCES**

305 Bienen B, Byrne BW, Houlby GT and Cassidy MJ (2006) Investigating six-degree-of-freedom loading of  
306 shallow foundation on sand. *Géotechnique* **56(6)**: 367–379,  
307 <http://dx.doi.org/10.1680/geot.2006.56.6.367>.

308 Byrne BW (2014) Laboratory scale modelling for offshore geotechnical problems. In ICPMG2014 – Physical  
309 Modelling in Geotechnics: Proceedings of the 8<sup>th</sup> International Conference on Physical Modelling in  
310 Geotechnics (Gaudin C and White D (eds)). CRC Press, Boca Raton, FL, USA, pp. 61–75.

311 Cathie D, Morgan N, and Jaeck C (2008) Design of sliding foundations for subsea structures. In *Proc. BGA*  
312 *International Conference on Foundations*. Dundee, Scotland, pp. 24–27.

313 Cheng N, Gaudin C, Cassidy MJ and Bienen B (2014) Centrifuge study of the combined bearing capacity of a  
314 hybrid foundation system. In *Proceedings ICPMG2014 – Physical Modelling in Geotechnics: Proceedings of the 8th International Conference on Physical Modelling in Geotechnics* (Gaudin C and  
315 White D (eds)). CRC Press, Boca Raton, FL, USA, pp. 487–492.

317 Chow SH, O’Loughlin CD, and Randolph MF (2014) Soil strength estimation and pore pressure dissipation for  
318 free-fall piezocone in soft clay. *Géotechnique* **64(10)**: 817–827, <http://dx.doi.org/10.1680/geot.14.P.107>.

319 Cocjin M and Kusakabe O (2013) Centrifuge observations on combined loading of a strip footing on dense  
320 sand. *Géotechnique* **63(5)**: 427–433, <http://dx.doi.org/10.1680/geot.11.P.075>.

321 Cocjin M, Gourvenec S, White D, and Randolph M (2014) Tolerably mobile subsea foundations – observations  
322 of performance. *Géotechnique* **64(11)**: 895–909, <http://dx.doi.org/10.1680/geot.14.P.098>.

323 Cocjin M, Gourvenec S, White D, and Randolph M (2015) Effects of drainage on the response of a sliding  
324 subsea foundation. In *Proceedings of the 3rd international symposium on frontiers in offshore geotechnics (ISFOG 2015), Oslo, Norway* (ed. V. Meyer). CRC Press London, UK, pp. 777–782.

326 Cocjin M, Gourvenec S, White D, and Randolph M (2016) Theoretical framework for predicting the response of  
327 tolerably mobile subsea installations. Paper under review.

328 De Catania S, Breen J, Gaudin C, and White DJ (2010) Development of a multiple-axis actuator control system.  
329 In *Proceeding Int. Conf. on Phys. Modelling in Geotechnics ‘10, Zurich* (Springman S, Laue J and  
330 Seward L (eds)). Taylor & Francis Group, London, UK, pp. 325–330.

331 Dean ETR, James RG, Schofield AN and Tsukamoto Y (1997) Theoretical modelling of spudcan behaviour  
332 under combined load. *Soils and Foundations* **37(2)**: 1–15, [http://dx.doi.org/10.3208/sandf.37.2\\_1](http://dx.doi.org/10.3208/sandf.37.2_1).

333 Feng X and Gourvenec S (2016) Modelling sliding resistance of tolerably mobile subsea mudmats.  
334 *Géotechnique* **66(6)**: 490–499, <http://dx.doi.org/10.1680/jgeot.15.P.178>.

335 Feng X, and Gourvenec S (2015) Consolidated undrained load-carrying capacity of subsea mudmats under  
336 combined loading in six degrees of freedom. *Géotechnique* **65(7)**: 563 – 575,  
337 <http://dx.doi.org/10.1680=geot.14.P.090>.

338 Feng X, Randolph MF, Gourvenec S and Wallerand R (2014) Design approach for rectangular mudmats under  
339 fully three-dimensional loading. *Géotechnique* **64(1)**: 51–63, <http://dx.doi.org/10.1680/geot.13.P.051>.

340 Gaudicheau P, Thorel L, Néel A, Audrain Ph, Loozaadaand C, and Monroy J (2014) Improvement of the  
341 IFSTTAR robot control system. In *Proceedings ICPMG2014 – Physical Modelling in Geotechnics: Proceedings of the 8th International Conference on Physical Modelling in Geotechnics* (Gaudin C and  
342 White D (eds)). CRC Press, Boca Raton, FL, USA, pp. 221 – 226.

344 Gourvenec S, and Randolph MF (2003) Effect of strength non-homogeneity on the shape of failure envelopes  
345 for combined loading of strip and circular foundations on clay. *Géotechnique* **53(6)**: 575–586,  
346 <http://dx.doi.org/10.1680/geot.2003.53.6.575>.

347 Green AP (1954) The plastic yielding of metal junctions due to combined shear and pressure. *J. Mech. Phys.*  
348 *Solids* **2(3)**: 197–211.

349 Hu P, Stanier A, Cassidy MJ and Wang D (2014) Predicting peak resistance of spudcan penetrating sand  
350 overlying clay. *J. Geotech. Geoenviron. Eng.* **140(2)**: 01013009,  
351 [http://dx.doi.org/10.1061/\(ASCE\)GT.1943-5606.0001016](http://dx.doi.org/10.1061/(ASCE)GT.1943-5606.0001016)

352 Kong V (2012) *Jack-up Reinstallation Near Existing Footprints*. PhD thesis, University of Western Australia,  
353 Crawley, Australia.

354 Martin, C and Randolph, M (2006) Upper-bound analysis of lateral pile capacity in cohesive soil. *Géotechnique*,  
355 **56(2)**, 141-145.

356 Morton JP, O'Loughlin CD, and White DJ (2014) Strength assessment during shallow penetration of a sphere in  
357 clay. *Géotechnique Letters* **4**(1st October 2014): 262 – 266, <http://dx.doi.org/10.1680/geolett.14.00049>.

- 358 O'Loughlin C (2015) Session report: offshore geotechnics at ICPMG 2014. *International Journal of Physical*  
359 *Modelling in Geotechnics* **15(2)**: 98–115, <http://dx.doi.org/10.1680/ijpmg.14.00040>.
- 360 Punrattanasin P, Nishioka H, Murata O and Kusakabe O (2003) Development of combined loading apparatus for  
361 centrifuge test. *International Journal of Physical Modelling in Geotechnics* **3(4)**: 1–13.
- 362 Randolph MF (2012) Offshore geotechnics – the challenges of deepwater soft sediments. In *Geotechnical*  
363 *Engineering State of the Art and Practice: Keynote Lectures from GeoCongress 2012* (Rollins K and  
364 Zekkos D (eds)). American Society of Civil Engineers, Reston, VA, USA, Geotechnical Special  
365 Publication no. 226, pp. 241–271.
- 366 Randolph MF and Hope S (2004) Effect of cone velocity on cone resistance and excess pore pressures. In *Proc.*  
367 *Int. Sym. on Eng. Practice and Performance of Soft Deposits*. Osaka, Japan, pp. 147–152.
- 368 Randolph MF, Gaudin C, Gourvenec SM et al. (2011) Recent advances in offshore geotechnics for deep water  
369 oil and gas developments. *Ocean Engineering* **38(7)**: 818–834,  
370 <http://dx.doi.org/10.1016/j.oceaneng.2010.10.021>.
- 371 Randolph MF, Jewell RJ, Stone KJ, and Brown TA (1991) Establishing a new centrifuge facility. In *Proc. Int.*  
372 *Conf. on Centrifuge Modelling, Centrifuge '91, Boulder* (Ko H-Y, and McLean FG (eds)). Balkema,  
373 Rotterdam, Netherlands, pp. 3–9.
- 374 Stewart DP and Randolph MF (1991) A new site investigation tool for the centrifuge. In *Proceedings of Int.*  
375 *Conf. on Centrifuge Modelling, Centrifuge '91, Boulder* (Ko H-Y, and McLean FG (eds)). Balkema,  
376 Rotterdam, Netherlands, pp. 531–538.
- 377 Zhang Y, Bienen B and Cassidy MJ (2013) Development of a combined VHM loading apparatus for a  
378 geotechnical drum centrifuge. *International Journal of Physical Modelling in Geotechnics* **13(1)**: 13–90,  
379 <http://dx.doi.org/10.1680/ijpmg.12.00007>.

## 380 **9. LIST OF FIGURES**

381 Figure 1. Schematic of loading arm and actuator system highlighting: (a) movement in the vertical direction, (b)  
382 movement in the horizontal direction, (c) loading arm profile view in the y-z plane, and (d) loading arm profile  
383 view in the x-z plane.

384 Figure 2. Positive sign convention for loads and displacements acting on a rectangular foundation.

385 Figure 3. Undrained shear strength profile with depth of soil model derived from a T-bar penetrometer test.

386 Figure 4. Model foundation: (a) schematic drawing along the long side ( $y$ - $z$  plane), and (b) schematic drawing  
387 along the short side ( $x$ - $z$  plane).

388 Figure 5. Schematic of the loading arm and model foundation movements through: (a) vertical motion of the  
389 loading actuator, (b) horizontal motion of the loading actuator, (c) rotation about  $x$ -axis of the foundation at the  
390 foundation hinge, and (d) rotation about  $y$ -axis of the foundation through the horizontal roller bearing.

391 Figure 6. Centrifuge tests loading program showing time-scales of the (a) vertical load,  $V$  and (b) horizontal  
392 displacement,  $u_y$  imposed on the mudmat foundation.

393 Figure 7. Time-scale plots of the vertical load ( $V$ ), horizontal displacement ( $u_y$ ), horizontal load ( $H$ ), vertical  
394 displacement ( $w_{(laser)}$ ), and foundation rotation about the  $x$  and  $y$  axes ( $\theta_{xx}$  and  $\theta_{yy}$ ) during: (a-e) touchdown of the  
395 foundation into the soil surface, (f-j) post-installation consolidation and undrained sliding cycles, and (k-o) first  
396 sliding and reconsolidation cycle.

397 Figure 8. Improved load control by reducing mechanical backlash.  
398

399 Figure 9. Comparison of foundation movements as measured by the actuator encoders, and independently by  
400 lasers in (a) vertical, and (b) horizontal direction.

401 Figure 10. Complete set of test showing: (a) foundation settlement (laser),  $w_{(laser)}$  and (b) horizontal load,  $H$   
402 plotted against horizontal displacement (encoder),  $u_{y(encoder)}$ , and mid-slide values of (c) foundation settlement  
403 (laser),  $w_{(laser)}$ , (d) horizontal load,  $H$ , and (e) rotation about the  $x$  and  $y$  axes,  $\theta_{xx}$  and  $\theta_{yy}$  plotted against cycle  
404 number,  $N$ .

405 Figure 11. (a) Post-touchdown and cyclic consolidation settlement plotted against cycle number,  $N$  (inset: void  
406 ratio profile with depth obtained at a free-field soil (virgin),  $e_0$  and within foundation footprint soil), and (b)  
407 overview photograph of foundation footprint after the test, showing peripheral berm formation.

408 Figure 12. Coefficient of sliding friction,  $\mu = H/V$  (a) during the first slide and (b) during the loading cycles  
409 plotted against normalised horizontal displacement (encoder),  $u_{y(encoder)}/B$ , and (c) mid-slide values plotted  
410 against cycle number,  $N$ .