

1 **The changing nature of groundwater control for temporary works**

2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28

Authors

Toby Roberts, Executive Chairman, WJ Groundwater, Watford
Martin Preene*, Technical Director, Richter Associates, Huddersfield, UK
William Powrie, Professor of Geotechnical Engineering, University of Southampton

***Corresponding Author**

Dr M Preene
Richter Associates
Independence House
Holly Bank Road
Huddersfield
HD3 3LX
Email: martin.preene@richter.global

Keywords

Geotechnical Engineering, Groundwater, Temporary Works

This revision 26 November 2022.

Words in the main text (excluding abstract and references): 5,284
Number of figures: 11
Number of tables: 3

The changing nature of groundwater control for temporary works

Abstract

Groundwater control for temporary works uses a range of methods to allow below-ground construction in stable and workably dry conditions. Common strategies include control by pumping (dewatering), with or without physical exclusion (cut-off walls). The fundamental principles of groundwater control have been well established for many decades, with practice-led improvements in hydrogeological understanding, materials and technology driving the gradual enhancement of methods over much of the 20th century. Contractors developed considerable expertise but commonly adopted an at least partly reactive approach to managing groundwater. Over the past 30 years this has had to change, partly as a result of increased environmental regulation of groundwater abstraction and discharge but also the requirement for shorter programme timescales for deeper and larger projects with the related need to consider and where necessary mitigate any potential adverse impact on neighbouring structures. This paper discusses how traditional groundwater control strategies are evolving in response to these challenges and the increasing focus on reducing carbon emissions in construction. Consideration is also given to the range of soil permeability suitable for the application of dewatering techniques, and the related issue of sources of risk and uncertainty in design and procedures for managing these.

Introduction

Groundwater control for temporary works involves the application of strategies to allow below-ground construction (e.g. for basements, sub-structures and tunnels) to be made in stable and workably dry conditions. These objectives can be achieved by a range of methods, some of which exploit significantly different geotechnical processes. The nature of temporary groundwater control techniques is initially discussed in the context of other geotechnical temporary works activities. This is followed by an exploration of the environmentally-driven and project-related factors that have driven change in groundwater control strategies over the past 30 years. It is noted that the universal requirements to reduce cost, minimise risk and shorten programs have to be considered in the context of environmental concerns and associated regulation and increasingly the imperative to curb greenhouse gas emissions. While much of this discussion is in the context of the regulatory regime in UK, similar environmental regulations now apply in almost all countries. The paper then summarises some of the developments in technology and techniques that have helped designers and contractors meet project requirements for the temporary control of groundwater within the prevailing regulatory constraints.

Monitoring, particularly of groundwater levels, flow rates and sometimes surface settlements, is typically an essential element of any groundwater control scheme. While developments in computing, communications and control systems have and continue to drive significant improvements in geotechnical monitoring systems, this is not the main focus of this paper.

Groundwater control in the context of other temporary works

Groundwater control is one of a variety of engineering methods potentially used for temporary works, with the objective of enabling construction, without necessarily forming part, of the permanent works. Pallet and Filip (2018) list a range of temporary works methods including excavation support and propping, formwork and falsework, scaffolding, temporary earthworks, and works to ensure the stability of temporary plant such as cranes, hoists and piling rigs.

80 Groundwater control is typically achieved via two strategies, which can be used separately
81 or in combination. These are control by pumping (known as dewatering) and control by
82 exclusion. Commonly used methods are summarised in Table 1. Further details are given in
83 Cashman and Preene (2021).

84
85 There is a useful distinction between pumping methods:

- 86 • Open pumping methods, which allow groundwater to enter an excavation, from
87 where it is then removed by pumping (Figure 1a). Because water is drawn directly
88 into the excavation, this can lead to instability if particles are washed from soil or
89 rock in the slopes and base of the excavation. This approach has the further
90 disadvantage that groundwater levels cannot be lowered in advance of excavation.
- 91 • Pre-drainage methods, which use wells to lower groundwater levels in advance of
92 excavation works (Figure 1b). The method draws water towards the wells, not into
93 the excavation, avoiding troublesome seepages and reducing the risk of
94 groundwater-induced instability.

95
96 Exclusion methods can be divided into three categories:

- 97 i. Cut-offs comprising very low-permeability walls or barriers physically inserted or
98 constructed in the ground (Figure 2a). The primary purpose of many cut-offs is to
99 provide physical support for an excavation (i.e., to act as a retaining wall), with
100 control of groundwater a potential secondary benefit. Cut-offs can be permanent,
101 for example secant piles, or temporary, for example sheet piles if they are removed.
- 102 ii. Ground treatments that reduce the permeability of the soil or rock in-situ around an
103 excavation (Figures 2b and 2c). Treatments can be permanent, for example
104 permeation grouting, or temporary, for example artificial ground freezing. These
105 techniques can be used for shaft sinking and tunnelling, or with cut-off walls to form
106 a base plug, Figure 2c.
- 107 iii. Use of a fluid pressure to counterbalance groundwater pressures in shafts and
108 tunnels (Figure 2d).

109
110 Compared with other temporary works activities, groundwater control has some particular
111 attributes:

- 112 i. The ground, and obviously groundwater, plays a key role in groundwater control, so
113 the success of a groundwater control strategy is highly dependent on having good
114 (and relevant) ground and groundwater investigation information. While this is not a
115 factor unique to groundwater control systems, the influence of groundwater
116 conditions is often more significant than for many other temporary works activities.
117 Each groundwater control technique has a specific range of application, particularly
118 in relation to the permeability of the ground (Figure 3a and 3b). There are examples
119 of groundwater control measures being ineffective when applied in the wrong
120 conditions (Preene, 2020).
- 121 ii. Many groundwater control methods are truly temporary – for example where a
122 pumped groundwater control system is used, groundwater levels will typically
123 recover to original levels in the days and weeks after pumping stops at the end of
124 construction. This also means that there is an important maintenance requirement –
125 if pumps break down, or if pumping is interrupted for other reasons, groundwater
126 levels will rise and the stability of the excavation may be compromised.
- 127 iii. Groundwater control is typically not codified in detail by national or international
128 design standards. For example, while Eurocode 7 (BS EN 1997-1:2004) includes a
129 section on dewatering, its requirements are limited to general comments that the
130 design should be based on the results of ground investigations, the objective of

131 design should be to achieve stable excavations, and that dewatering systems should
132 be reliable and subject to monitoring.
133 iv. The activities involved in the control of groundwater, particularly abstraction and
134 discharge, have the potential to impact on the environment, groundwater resources
135 or neighbouring structures well beyond the site boundary. As a result, some
136 groundwater control techniques are subject to national or local regulation (e.g. by
137 the Environment Agency in England). The regulatory approval process may take
138 several months and can impact construction programmes.
139

140 This puts most groundwater control methods into a category where expertise is
141 concentrated in a small number of specialist organisations. According to Powrie (1990),
142 'Dewatering is regarded by the civil engineering profession in general as something of an art,
143 the practice of which is best left to the cognoscenti', and this is still largely the case today.
144 The current paper discusses some of the present and future challenges of groundwater
145 control applications for temporary works, with the objective of sharing knowledge and
146 experience in this field.
147

148 **Overview of factors driving the evolution of groundwater control methods**

149 While the fundamental principles have not changed, groundwater control methods - like
150 many temporary works activities - have undergone a largely practice-led evolution over
151 several decades; some examples of this evolution are given in Table 2. This has been, and
152 continues to be, driven by:

- 153 • Improvements in materials, plant and equipment and technology (including data
154 systems, control and power supply).
- 155 • Deeper understanding of hydrogeology and design methods, including better and
156 more rapid access to groundwater monitoring data.
- 157 • Demand-led need for bigger, deeper and more complex excavations with less
158 interference with construction operations from methods to physically support the
159 soil or rock.
- 160 • Regulation, in the late 20th century relating mainly to direct environmental impacts
161 of abstraction and discharge (such as protecting groundwater resources) but
162 increasingly focusing on curbing greenhouse gas emissions (principally carbon
163 dioxide, often abbreviated to "carbon") as well.
- 164 • The ever-present need to reduce costs and to complete projects more rapidly with
165 outturn costs close to pre-construction estimates.
166

167 Developments in technology and hydrogeological understanding, combined with project-led
168 demand, have led to a widening in the complexity and range of application, and
169 improvement in the efficiency and effectiveness of, pumped groundwater control systems.
170 There is also a history of technology transfer, whereby a method used in other industries
171 (e.g. mining) is subsequently used in construction temporary works. This is one way that
172 better groundwater control techniques may be developed in the future.
173

174 Commercial pressures to control and where possible reduce costs are always present in the
175 construction industry. Changes that impact on temporary works and groundwater control
176 strategy also arise from several other quarters including evolving environmental regulation,
177 societal demands relating to climate change, project scope and risk management.
178

179 Examples of the influence of regulation include the banning of potentially toxic ingredients
180 in chemical grouts, and increased control (and eventual abandonment) of compressed air
181 tunnelling in response to identified health risks to workers. Increasing environmental

182 regulation of pumped groundwater control methods may also influence the future
183 development and / or application of such methods.

184

185 The remainder of this paper will review the challenges of developing appropriate schemes
186 for temporary works groundwater control, focusing on the future challenges of increased
187 regulation and the need to assess environmental impacts and carbon emissions between
188 very different techniques. Project-related requirements and some recent developments in
189 techniques and technology are also considered.

190

191 **Environmentally-driven factors**

192 *Regulatory requirements*

193 Groundwater resources have been formally protected by regulation in parts of the UK since
194 the Water Resources Act 1963, with later provision to license and protect abstractors.
195 Dewatering (for construction and for mines and quarries) was formerly largely exempt from
196 regulatory oversight but recently The Water Abstraction and Impounding (Exemptions)
197 Regulations 2017 have removed this exemption in England and Wales. For the construction
198 industry the consequence of this is that, with a few exceptions relating to short term
199 pumping at very low flow rates, groundwater pumping activities now generally require
200 consents for abstraction and discharge of groundwater. The regulations distinguish between
201 transfer of groundwater from one source of supply (groundwater) to another (to a lake or
202 river) and removal of water from the groundwater system (e.g. discharge to sewer).
203 Significant exemptions to the licensing requirements may also apply where the abstracted
204 groundwater from a dewatering system is recharged back to the aquifer. Responsibility for
205 managing water resources was devolved away from Central Government in the UK so that
206 the regulatory authority, exemptions, and procedures differ between different nations in the
207 UK.

208

209 Obtaining the necessary consents requires the design team to determine, in advance of
210 construction, the abstraction flow rate required to achieve the drawdown needed to
211 maintain stability of the excavation or structure. This information feeds into an assessment
212 of the possible impact on groundwater-dependent features, licensed abstractors and
213 neighbouring structures. Some precision is required in this process since an overestimate
214 may require enhanced mitigation measures and could possibly result in denial of consent if
215 the regulatory authority considers that water resources or groundwater dependent features
216 may be at risk. On the other hand, an under-estimation runs the very real possibility of
217 significant delay to the works if actual flow rates required are found to be above the licensed
218 rate such that a new consent application is required. The precision needed, particularly in
219 medium to low permeability soils, is often greater than that required to design the
220 dewatering scheme. The need for precision in flow assessments has greatly expanded the
221 requirement for pumping tests for projects where a pumped groundwater control scheme is
222 planned. It has also spawned the development of non-standard pumping tests using short
223 screens or multiple wells to maximise the relevance of the parameters obtained; examples
224 are given in Roberts and Holmes (2011) and Holmes et al (2018).

225

226 Internationally, regulations to protect water resources, including groundwater resources,
227 now exist in most countries. The arrangements may differ appreciably, reflecting local
228 conditions; but the requirement for reliable prior assessment of groundwater control flow
229 rates and water quality together any associated potential for adverse impact on the
230 environment or neighbouring structures is almost universal.

231

232 *Societal demands relating to climate change*

233 Reduction in emissions of greenhouse gases, including embedded emissions associated with
234 construction materials, is now a major driver for the design of both temporary and
235 permanent works. The European Federation of Foundation Contractors (2022) notes that
236 construction materials, particularly concrete and steel, have high embedded emissions and
237 designers should focus on minimising their use. Controlling groundwater levels and pore
238 water pressures can be an effective strategy to reduce material requirements, particularly
239 for temporary works. For example, the required depth of a concrete secant pile embedded
240 retaining wall will be partly controlled by loading from external pore water pressures and it
241 may be feasible to reduce the depth, and corresponding material requirements, if external
242 pore water pressures can be lowered or eliminated during construction. Once the structure
243 is complete it will typically be designed to have sufficient weight and structural integrity to
244 resist groundwater pressures. This may well include permanent props (e.g. floor or roof
245 slabs) at multiple levels, not present during construction.

246
247 An interesting case study is given by Casey et al (2015), which compared solutions to
248 mitigate high groundwater uplift pressures for a large station box in East London using either
249 concrete tension piles or groundwater pumping. This showed that the carbon emissions
250 embedded in the tension pile solution were significantly greater than those associated with
251 the pumping solution even if pumping is continued for the full 80-year design life of the
252 structure. Direct comparisons are not straightforward and may change over time. For
253 example, the carbon emissions for tension piles are almost entirely indirect emissions
254 associated with the concrete and steel whereas for the pumping solution the emissions are
255 dominated by the operational power to drive pumps, which would be expected to reduce
256 over time as electricity is increasingly generated from renewable and low carbon sources.

257

258 **Project-related considerations - risk management**

259 Groundwater control has long been considered a high-risk construction activity for a range
260 of reasons including:

- 261 • Lowering groundwater levels increases the vertical effective stress on the strata
262 below the initial groundwater level, which inevitably results in the compression /
263 consolidation and settlement of the ground. While the risk of ground settlements
264 large enough to cause damage / distress to nearby structures can be a concern in
265 soft soils it may be overstated, particularly for dense granular soils or stiff clays
266 where even significant lowering of groundwater levels for temporary works
267 purposes may result in modest settlements. Screening and assessment of structures
268 is typically required to determine the level of risk concerned.
- 269 • The hydraulic gradient towards a pumping system in a granular soil is relatively
270 shallow so that the influence of a dewatering system sometimes extends to a
271 considerable distance beyond the site boundary. It is likely to be rather greater than
272 the zone of direct influence generally associated with excavations, retaining walls
273 and tunnels, where the maximum lateral extent of the settlement trough is generally
274 equivalent to approximately the depth of the structure.
- 275 • Lowering the groundwater level beyond the site boundary can adversely impact
276 groundwater-dependent features or existing licensed abstractors, and can mobilise
277 any existing groundwater contamination. These risks need to be considered,
278 including mitigation measures where necessary, in the environmental consent
279 application process. The groundwater control design process often needs to be fairly
280 advanced before it becomes apparent whether any concerns are potentially
281 significant.
- 282 • The time to process license applications is quoted by the various regulatory
283 authorities as several months, from when a valid application has been made. This

284 period does not include the time required to gather the necessary information,
285 prepare reports and impact assessments and the time for any pre-application
286 discussions with the regulatory authorities - all of which may considerably extend
287 the application process.

288
289 Some hydrogeological settings may present significant risks that need to be addressed but in
290 other settings the risks may be overstated or misunderstood owing to common
291 misconceptions. For example, Figure 4a illustrates a ground profile where lowering the
292 groundwater levels in a sandy gravel (typical of the River Terrace Deposits in London) could
293 result in the underdrainage of the overlying soft silty clay (of alluvial origin), with a risk of
294 surface settlement and the potential to impact adjacent structures (if present). A case in
295 which similar pumping from a coarse granular layer below alluvial clays and peat resulted in
296 settlement damage to buildings in the vicinity is reported by Powrie (2014), and discussed in
297 Preene (2020).

298
299 The ground profile in Figure 4b is similar but the natural groundwater level is already within
300 the gravels below the soft clays; hence lowering the groundwater level in this case cannot
301 underdrain the soft alluvial clay and the risk of damaging ground settlements is likely to be
302 minimal.

303
304 The contract specification for a recent large infrastructure project in London included a
305 requirement that groundwater pumping could only be used in the temporary works for a
306 deep excavation providing there was no change in pore water pressure beyond the site
307 boundary. This effectively prohibited dewatering in the Thanet Formation (formerly known
308 as the Thanet Sand) and Chalk Group, which comprises the London Lower Aquifer. The
309 London Lower Aquifer has been subject to very substantial changes in groundwater level
310 over the past 150 years. Initial overexploitation of groundwater resources from the mid 19th
311 century led to a reduction in groundwater levels of up to approximately 70 m in central
312 London. This was followed by a period of significant recovery in groundwater levels from
313 about 1950. Over the past 40 years it has been recognised that allowing groundwater levels
314 to fully recover would have an adverse impact on the stability and serviceability of critical
315 infrastructure and property in central London and a process of managed control has been
316 implemented (Environment Agency 2018). Given this background a contractual prohibition
317 on temporary dewatering in the Lower Aquifer made no practical, commercial or
318 environmental sense and was largely circumvented during construction.

319 320 **Developments in technologies and techniques**

321 *Electrically powered plant*

322 The evolution of project requirements and regulations outlined above have and will continue
323 to drive changes in groundwater control techniques and strategies in the construction
324 industry. There has long been a trend away from diesel towards electrically powered
325 pumping equipment due to a range of factors including:

- 326 • Reduced noise (particularly important for continuous 24 hr pumping)
- 327 • Reduced maintenance down time and costs
- 328 • Reduced need for fuel and oils on site, minimising risk of leakage and
329 contamination
- 330 • Improved options for system control such as automatic starting of standby pumps
- 331 • Improved options for plant performance monitoring (including remote on-line
332 monitoring)
- 333 • Improved options for warning and alarm systems
- 334 • Improved air quality (particularly in tunnels, shafts and other confined spaces).

335 The increasing use of renewable sources to generate mains electrical power and the
336 overriding requirement to reduce greenhouse gas emissions has added impetus to this trend
337 and a new focus on electrification of installation plant, particularly for in-tunnel installations
338 (Figure 5).

339
340 One of main drive shafts for the Tideway Project in central London was located 70 m away
341 from a major public water supply well abstracting from the chalk, which forms the major
342 part of the Lower Aquifer (Figure 6). Abstraction flows for the supply well were
343 approximately 60 l/s, but subject to demand and frequently interrupted. Groundwater levels
344 in the Lower Aquifer at the shaft fluctuated in response to the public water supply well
345 stopping and starting. When operating continuously the supply well achieved a drawdown
346 (relative to unpumped water levels) at the shaft of approximately 12 m, which was just
347 sufficient to allow construction of the TBM (tunnel boring machine) launch adits from the
348 shaft using sequential excavation methods (SEM) and sprayed concrete lining (SCL)
349 techniques.

350
351 The traditional approach would have been to design a dewatering scheme capable of
352 achieving 12 m of drawdown at the shaft and to run this continuously so that, when
353 pumping from the public water supply was interrupted, groundwater levels would remain
354 below the target level for safe adit construction. This would have resulted in approximately
355 24 m of drawdown when the public water supply pump was operational, with groundwater
356 of drinking water quality being discharged to the Thames, wasted energy consumption for
357 the dewatering system operation and the risk of adverse impact on other licensed
358 groundwater abstractors in the vicinity. The solution was to use variable speed drive
359 dewatering pumps, programmed to respond to changes in groundwater level in a
360 piezometer at the site boundary.

361
362 Figure 7 shows the Lower Aquifer groundwater level at the shaft, the target groundwater
363 levels and the dewatering system abstraction flow rate. The dewatering system flow rate can
364 be seen to be near zero, rising to 40-50 l/s when the public water supply pumping is
365 interrupted. Periods of excessive drawdown occurred when the public water supply was
366 operated at elevated flow rate; and the prolonged period of continuous dewatering
367 pumping in January to March 2019 corresponded to the cessation of pumping from the
368 public water supply well following the mechanical failure of the pump. This is an interesting
369 example of how operation of a resource that is protected by regulation (the public water
370 supply well) can adversely impact construction works, and how modern electrical pumping
371 systems can be controlled to mitigate the risk.

372
373 *In-tunnel/shaft dewatering techniques and strategies*

374 Tunnelling and shaft sinking using the sequential excavation method (SEM) with sprayed
375 concrete lining (SCL) support has several advantages over other techniques including speed
376 of construction and flexibility in shape. The technique exploits the inherent strength of the
377 ground to allow rapid sequential excavations, each of which is supported by SCL before the
378 next advance. Conventional dewatering techniques for SEM tunnels involve vertical or
379 inclined wells installed from the ground surface in advance of the face, avoiding both the
380 artesian conditions and logistical challenges inherent with the installation of in-tunnel wells
381 that penetrate out through the tunnel lining. Over the last 30 years, however, in-tunnel and
382 in-shaft dewatering techniques have been applied, both to control groundwater where
383 surface access is difficult and to gain direct access to the water bearing strata at tunnel level
384 (Figure 8). The most efficient approach is often a combination of surface and below ground
385 dewatering techniques.

386

387 Roberts et al (2015) and Soler et al (2016) give examples of in-tunnel wellpoints that are
388 particularly appropriate when targeting thin or intermittent granular beds of water-bearing
389 soils where a closer well spacing of 1 to 3 m may be required. Prior to the mid-1990s,
390 standard surface dewatering and installation equipment was taken underground but over
391 the last 25 years specialist in-tunnel and in-shaft systems, equipment and techniques have
392 been developed. Figure 9 shows a compact in-shaft ejector station with inclined ejector
393 wells drilled inclined through the concrete secant pile wall shaft lining to reduce external
394 hydrostatic loads and to control seepage into the base of the shaft. Surface access
395 restrictions meant that a conventional vertical well system outside of the shaft was not an
396 option. Installation of wellpoints or ejector wells from a tunnel or shaft into pressurised
397 granular soils (with a groundwater head significantly above the level of the drill rig) requires
398 the use of a specialist insert grouted into the tunnel or shaft structural lining. The insert is
399 fitted with a blowout preventer (BOP) to control ground loss and water flow during
400 installation. Lost bit drilling is then used to drill through the insert to place casing to the
401 target depth; the well screen and liner are then installed as the casing is withdrawn.

402

403 An example of an in-tunnel dewatering scheme for a cross passage between two running
404 tunnels (previously driven by TBM) is illustrated in Figure 10a and 10b. A water-bearing
405 granular bed had been identified at and below the tunnel invert, which was targeted with an
406 array of downward inclined wellpoints installed from one of the TBM drives. The dewatering
407 strategy involved installation of the initial wellpoint array with procedures for monitoring
408 and 'toolbox' measures (a term used in tunnelling to describe specific additional
409 groundwater control measures, applied in response to observed conditions). Here these
410 toolbox measures comprised supplementary wellpoint installations, only installed if
411 required. Probe drilling, shown in red, would then be carried out to prove stable conditions
412 in advance of the cross-passage excavation.

413

414 *Artificial recharge systems*

415 Artificial recharge of groundwater back to the ground has become an increasingly important
416 groundwater control strategy for several reasons, including as an environmental risk
417 mitigation measure (e.g. Holmes et al 2018); as a settlement risk mitigation measure (e.g.
418 Roberts and Holmes 2011; Powrie and Roberts 1995); and as a means of disposal where
419 other options are not available or have a high cost. In Tel Aviv, Israel, discharge of
420 groundwater to sewer is prohibitively costly so that almost all discharge from construction
421 dewatering systems in the shallower aquifer is recharged. This is a deliberate policy to
422 preserve groundwater resources. Access and space constraints in the city mean that water
423 from dewatering systems is generally recharged to a deeper aquifer 50 to 200 m below the
424 site.

425

426 Successful design of an artificial recharge system usually requires a data from a relatively
427 detailed hydrogeological investigation supported by appropriate, often numerical,
428 modelling. The investigation is required to provide the ground profile, groundwater levels,
429 basic hydrogeological modelling parameters, realistic values for well yields, and to assess the
430 risk of loss of recharge capacity due to clogging. In addition to investigating the design of
431 the abstraction system, the modelling also needs to provide a good understanding of the risk
432 and extent of any feedback (between artificial recharge flows and the pumping wells), and of
433 the extent and potential impact of any local increases in groundwater level around the
434 location of recharge wells, trenches or infiltration ponds. Successful implementation and
435 operation of an artificial recharge system requires real-time monitoring of flows and
436 groundwater levels to identify any capacity loss in the system and allow development of a

437 strategy and programme for the redevelopment and cleaning of the recharge wells to
438 recover capacity.

439

440 *Vacuum deepwells*

441 As noted in Table 2, ejector wells have been in regular use in North America since the 1950s.
442 The first major use of ejectors in the UK was for the Conwy crossing in North Wales (Powrie
443 and Roberts 1990). Ejector wells are an effective technique for providing vacuum assisted
444 drainage in fine granular soils with permeability in the range 10^{-7} to about 10^{-5} m/s. Ejectors
445 are based on the venturi effect, whereby water is pumped through the constriction of a
446 nozzle to reduce pressure and provide suction according to Bernoulli's Principle. Ejectors can
447 pump both air and water hence, if the well head and annulus are sealed, when the well is
448 emptied of water a vacuum will develop, which assists the drainage of water from fine-
449 grained soils. An important benefit of ejector wells is that they do not require a flow of
450 groundwater and can be run 'dry' for extended periods without damage. Ejector wells have
451 several drawbacks, however:

- 452 • They have low mechanical efficiency, hence high energy consumption relative to the
453 abstraction flow rate.
- 454 • The system requires priming, which effectively prevents the implementation of an
455 automatic restart if leakage causes loss of the recirculating water.
- 456 • A single high pressure supply pump will operate 40 or more ejector wells, so that a
457 fault with the supply pump immediately leads to the outage of many wells (the same
458 is true for a wellpoint system).

459

460 The centrifugal borehole submersible pumps used in deepwells do not suffer these
461 drawbacks but cannot pump air and rely on the flow of groundwater for cooling, lubrication
462 and hydrodynamic stability. If the well head and annulus are sealed, however, a surface
463 vacuum pump can be used to apply a vacuum to the well liner to achieve vacuum assisted
464 drainage. A simple assessment of well yields using the empirical methods from Preene and
465 Powrie (1993) gives the results in Table 3, as an aid to the selection of such systems at the
466 design stage.

467

468 The minimum yield for a submersible pump is approximately $0.15 \text{ m}^3/\text{hr}$, which from Table 3
469 suggests that flow rates may be viable for vacuum deepwells in aquifers >5 m thick with
470 permeability $>2 \times 10^{-6}$ m/s. Apart from the significant difficulty in reliably assessing
471 permeability and well yield in such fine-grained soils there are also other factors in play, such
472 as redundancy or conservatism in design which results in a greater number of wells for a
473 scheme and a corresponding reduction in individual well yield. A lower practical permeability
474 limit for vacuum deepwells in a 5 m thick aquifer is approximately in the range 2×10^{-6} to $5 \times$
475 10^{-6} m/s.

476

477 The range of applications of groundwater control pumping methods in granular soils,
478 Figure 3a, which dates from the mid-1990s, has been updated to reflect some of the
479 developments noted in this paper, see Figure 11. The key changes are,

- 480 • Inclusion of vacuum deepwells as a recognised technique which covers some of the
481 range which was formerly the exclusive preserve of ejector wells,
- 482 • Recognition that, for shallow drawdowns, single stage wellpoints are typically
483 effective and more efficient than ejector wells at targeting soils with a permeability
484 $<1 \times 10^{-5}$ m/s, and
- 485 • Recognition that sumps and drains are effective for drawdowns of 1 or 2 m providing
486 the permeability is not so low that vacuum assisted drainage is required.

487 Note that Figure 11 is an aide to understanding the range of application of the various
488 pumping methods for groundwater control rather than a primary design tool. It also gives
489 some guide to risk in situations where the range of permeability values at a site are close to
490 or reach across one or more boundaries. Drawdowns greater than the 20 m vertical scale
491 used in Figure 11 can be achieved but invariably require high quality geotechnical and
492 hydrogeological information and expert advice to confirm that conditions are suitable.
493 Techniques which have depth limitations, such as suction lift for wellpoints, require the
494 pumps to be installed at the standing groundwater level to achieve the maximum
495 drawdowns shown.

496

497 Figure 11 does not of course apply for cemented soils or rock where open pumping is often
498 significantly more widely applicable although other factors, such as poor discharge water
499 quality due to entrainment of fine particles, can be a factor in selection of methods.

500

501 **Conclusions**

502 Groundwater control strategies for temporary works have evolved as a result of
503 improvements in materials, equipment and techniques. The need for new equipment and
504 strategies for groundwater control have also been driven by advances in other construction
505 techniques, for example the increased use of SEM and SCL methods for shafts and tunnels.
506 In the UK and many other countries environmental regulation, which aims to protect
507 groundwater resources, groundwater-dependent ecology and the water quality of ponds,
508 watercourses and the sea, has become a major driver for changes in working practices
509 particularly over the last 30 years. Improvements in hydrogeological understanding have led
510 to enhancements and an increased range of applicability of some dewatering techniques.

511

512 The principal driver for change in construction industry practices over the coming years is
513 likely to be the requirement to curb greenhouse gas emissions. Cement and steel are both
514 carbon intensive to produce and their use is typically the largest contribution to the carbon
515 emissions of a construction project. Minimising their use is now a guiding principle for
516 designers. and is an increasingly significant factor in the selection and design of temporary
517 works groundwater control measures. Temporary groundwater cut-offs, such as sheet-piles
518 that can be removed, should minimise emissions with the added benefit of preserving
519 groundwater flow paths in the long term. The use of groundwater cut-offs incorporating
520 concrete/cement or steel that are not required for the permanent works and that will
521 remain as a permanent barrier to flow, will need much greater scrutiny of carbon emissions
522 in future. The same applies to temporary anchors or tension piles that are used to resist
523 hydrostatic uplift or lateral loads. Groundwater pumping systems have relatively low carbon
524 emissions, which makes them an attractive alternative method for temporary control of
525 groundwater ingress or excess pore pressures.

526

527 There can be tension between minimising greenhouse gas emissions on the one hand and
528 short-term environmental protection and construction risk on the other. Over the last 30
529 years there has been increasing focus by clients and contractors on restricting the use of
530 groundwater pumping systems (dewatering systems) in favour of groundwater exclusion
531 methods (cut-offs) with the aim of reducing risk of off-site impacts. The complex and
532 sometimes lengthy regulatory regime for obtaining environmental permits for pumping
533 methods has served to further drive this trend, but an increasing focus on reducing
534 greenhouse gas emissions may go some way towards reversing it.

535

536 **References**

537 BS EN 1997-1:2004 + A1:2013. UK National Annex to Eurocode 7. Geotechnical Design:
538 General Rules. British Standards Institution, London.
539
540 Cashman, P M and Preene, M. (2021). Groundwater Lowering in Construction: A Practical
541 Guide to Dewatering, 3rd edition. CRC Press, Boca Raton.
542
543 Casey, G, Pantelidou, H, Whitaker, D, O’Riordan, N, Soga, k and Guthrie, P. (2015) Capital &
544 operational carbon - an assessment of the permanent dewatering solution at Stratford
545 International Station. Geotechnical Engineering for Infrastructure and Development: XVI
546 European Conference on Soil Mechanics and Geotechnical Engineering. Eds Winter, M C,
547 Smith, D M, Eldred, P J L and and Toll, D G. ICE Publishing, London.
548
549 Environment Agency. (2018). Management of the London Basin Chalk Aquifer. Status Report
550 – 2018. Environment Agency, London.
551
552 European Federation of Foundation Contractors. (2022). Sustainability guides for foundation
553 contractors, Guide No. 1 Carbon reduction, First Edition. European Federation of Foundation
554 Contractors.
555
556 Holmes, G J, Roberts, T O L and Lee, M A. (2018). A case study of construction dewatering in
557 Northern Province Chalk. Engineering in Chalk: Proceedings of Chalk 2018 conference. Eds
558 Lawrence, J A, Preene, M, Lawrence, UK and Buckley, R. ICE Publishing, London.
559
560 Pallett, P F and Filip, R. (2018). Temporary Works: Principles of Design and Construction, 2nd
561 edition. ICE Publishing, London.
562
563 Powrie, W. (1990). Legal Aspects of Construction Site Dewatering for Temporary Works.
564 Unpublished MSc dissertation, Kings College, London.
565
566 Powrie, W. (2014). Soil Mechanics: Concepts and Applications, 3rd edition. Spon, Abingdon.
567
568 Powrie, W and Roberts, T O L. (1990). Field trial of an ejector well dewatering system at
569 Conwy, North Wales. Quarterly Journal of Engineering Geology, Vol 23, pp169–185.
570
571 Powrie, W and Roberts, T O L. (1995). Case history of a dewatering and recharge system in
572 chalk. Géotechnique, 45, No.4, pp599–609.
573
574 Preene, M. (2020). Conceptual modelling for the design of groundwater control systems.
575 Quarterly Journal of Engineering Geology and Hydrogeology, 54, qjegh2020-138.
576
577 Preene, M and Chrimes, M M. (2021). Groundwater lowering for construction of the Kilsby
578 Tunnel – geological and geotechnical aspects. Proceedings of the Institution of Civil
579 Engineers, Engineering History and Heritage.
580
581 Preene, M and Powrie, W. (1993). Steady-state performance of construction dewatering
582 systems in fine soils. Géotechnique, 43, 2 pp191–205.
583
584 Preene, M, Roberts, T O L and Powrie, W. (2016). Groundwater Control – Design and
585 Practice, 2nd Edition. Construction Industry Research and Information Association, CIRIA
586 Report C750, London.
587

588 Soler, R, Colace, A, Stärk, Zeizig, W and Roberts, T O L. (2016). In-tunnel depressurisation for
589 SCL Tunnels at Whitechapel and Liverpool Street Stations. Crossrail Project: Infrastructure
590 Design and Construction (Black, M, ed) ICE Publishing, London, pp33–51.
591
592 Roberts, T O L and Holmes, G. (2011). Case study of a dewatering and recharge system in
593 weak Chalk rock. Proceedings of the 15th European Conference on Soil Mechanics and
594 Geotechnical Engineering, Athens, Greece, 12–15 September 2011. Geotechnics of Hard
595 Soils – Weak Rocks (part 4). Eds Anagnostopoulos, A, Pachakis, M, Tsatsanifos C H. IOS Press,
596 Amsterdam, The Netherlands, pp1561-1566.
597
598 Roberts, T O L, Smith, R, Stärk, A and Zeizig, W. (2015) Sub-surface dewatering for an
599 inclined SCL tunnel. Geotechnical Engineering for Infrastructure and Development: XVI
600 European Conference on Soil Mechanics and Geotechnical Engineering. Eds Winter, M C,
601 Smith, D M, Eldred, P J L and and Toll, D G. ICE Publishing, London, pp2853–2858.
602
603 The Water Abstraction and Impounding (Exemptions) Regulations 2017. Statutory
604 Instrument 2017 No. 44 Water Resources, England and Wales. HMSO, London.
605
606 Water Resources Act 1963. HMSO, London.
607

Table 1: Groundwater control methods commonly used in temporary works

Method	Applications	Example methods
Pumping methods (also known as dewatering methods)		
Open pumping	Can be used for control of surface water run-off and shallow groundwater (including perched water and residual seepages into excavation) in rock and coarse-grained soils, where the flow of groundwater into the excavation is unlikely to cause instability. May generate silt or sediment laden discharge water, causing environmental problems if pumped water is not adequately treated prior to discharge	<ul style="list-style-type: none"> • Sump pumping • Drainage ditches • French drains
Pre-drainage pumping	Applicable to a wide range of soils and rocks, including cases where ensuring stability of the excavation is a key factor. Artificial recharge may be used to return some or all of the pumped water back to the ground	<ul style="list-style-type: none"> • Wellpoints and suction wells • Horizontal wellpoints laid by trenching machine • Deepwells with submersible pumps • Ejector wells • Electro-osmosis
Exclusion methods		
Cut-off walls	Cut-off walls are typically vertical. Some methods can be used to form structural elements of the permanent works (e.g. concrete diaphragm walls or secant pile walls used to form basement walls). Other methods are temporary only and can be removed at the end of construction so that no permanent groundwater barrier remains.	Permanent methods <ul style="list-style-type: none"> • Vibrated beam walls • Cement-bentonite slurry trench walls • Soil-bentonite slurry trench walls • Concrete diaphragm walls • Concrete secant pile walls Temporary methods (if removed at end of construction) <ul style="list-style-type: none"> • Steel sheet-pile walls • Steel combi-pile walls
Ground treatment	Specialist methods reduce the permeability of the in-situ soil or rock; often there is a corresponding increase in strength. Some methods can be used to form non-vertical elements including barriers to enclose tunnels and other underground spaces or to form basal plugs below excavations.	Permanent methods <ul style="list-style-type: none"> • Permeation grouting • Rock fracture grouting • Jet grouting • Mix-in-place grouting methods Temporary methods <ul style="list-style-type: none"> • Artificial ground freezing
Application of fluid counter pressures	Applicable to confined excavations (typically tunnels and shafts) which can be isolated so that fluid counter pressure can be applied	<ul style="list-style-type: none"> • Compressed air tunnelling and shaft sinking • Earth pressure balance (EPB) tunnel boring machines (TBMs) • Slurry tunnel boring machines (TBMs) • Caisson sinking by the wet caisson method

610
611

Table 2: Historical development of selected groundwater control methods (based on information from: Cashman and Preene, 2021; Preene and Chrimes, 2021)

Method	Key principles of the method	First reported applications	Later improvements in methods
Pumping methods			
Wellpoint systems	Closely-spaced small diameter wells pumped by a suction system, installed in rings around or lines alongside excavations.	Abyssinian tube wells (also known as Norton tube wells) were developed and used by the British Military from the 1860s onwards.	Modern wellpoint systems typically install wells by water jetting, a method that was developed by Thomas Moore in 1925 in New Jersey, USA. Plastic materials, used for wellpoint risers and pipework, were introduced in the 1960s and 1970s Installation of wellpoints from inside tunnels was perfected on the Storebaelt project in Denmark in the 1990s From the 2000s onwards energy efficiency and emissions controls promote the use of electrically driven pumps and lower emission diesel units
Deepwell systems	Widely spaced wells, pumped by electric submersible pumps in modern practice.	Very early applications were by Marc Isambard Brunel when sinking the Rotherhithe Shaft on the Thames Tunnel in 1824 and by Robert Abraham in 1830, during foundation construction for the Westminster New Bridewell prison. The first large scale application was by Robert Stephenson in 1835–6 for the Kilsby Tunnel on the London to Birmingham Railway.	Electrical submersible pumps were first used in dewatering wells in Germany from 1896, including for the Berlin U-Bahn underground railway. Plastic materials, used for well screens and pipework, were introduced in the 1960s and 1970s Developments in electronic equipment allowed automation of temporary pumping systems to be introduced from the 1980s Improved field sensors, internet connectivity and wireless data networks led to a dramatic expansions of remote monitoring and control systems in the early 2000s
Ejector well systems	Arrays of wells pumped by a water-driven nozzle and venturi system.	Jet pumps (the basis of the method) were developed in the 1850s, but were first applied for groundwater control in the United States in the 1950s, with jet pumps as used in water supply wells.	
Exclusion methods			
Steel sheet-piling	Interlocking steel sections driven or pushed into the ground to form a continuous wall	Cast-iron sheet piles were first used in the early 1820s on the North Pier of Bridlington Harbour.	In the early 1900s the method of steel sheet-piles connected by interlocks (clutches) was developed by Tryggve Larssen, in Germany.

Method	Key principles of the method	First reported applications	Later improvements in methods
Permeation grouting and rock grouting	Injection of fluid grouts to block water pathways without disturbing the soil or rock structure	The first applications of cement grouting were in France between 1797 and 1818, and the method was first applied in the UK in the 1850s.	Chemical grouts were developed in the 1920s. These have a lower viscosity, allowing penetration of smaller soil pores and rock fissures. The first reliable method was the Joosten process, patented in Germany in 1925.
Artificial ground freezing	Low temperature refrigerant is circulated in closely-spaced freezeholes, to create a wall of frozen groundwater and soil/rock.	The method was first used in the UK for shaft sinking at a colliery in South Wales in 1862.	From the 1960s onwards liquid nitrogen was used on some projects as an alternative to chilled brine.
Compressed air tunnelling	Tunnels and shafts under construction are pressurised with air to approximately balance groundwater pressures.	A system for compressed air tunnelling was patented in 1830 by Sir Thomas Cochrane.	From the mid 20 th century the health risks to workers in compressed air environments gained greater attention. By the Millennium the use of compressed air methods in most countries was limited to carefully controlled conditions with specialist medical supervision.


612

613 Table 3: Assessment of well yields in fine soils using empirical methods from Preene and
 614 Powrie (1993) with shading indicating viable deepwell flow rates.

Screen Length	Permeability			
	$5.0 \times 10^{-7} \text{ m/s}$	$1.0 \times 10^{-6} \text{ m/s}$	$2.0 \times 10^{-6} \text{ m/s}$	$1.0 \times 10^{-5} \text{ m/s}$
	Well yield	Well yield	Well yield	Well yield
1 m	0.008 m ³ /hr	0.017 m ³ /hr	0.034 m ³ /hr	0.170 m ³ /hr
5 m	0.042 m ³ /hr	0.085 m ³ /hr	0.017 m ³ /hr	0.848 m ³ /hr
10 m	0.085 m ³ /hr	0.170 m ³ /hr	0.339 m ³ /hr	1.696 m ³ /hr


615
 616

617



618
619


a) Open pumping (example shown is a sump pumping system)



620
621
622
623
624
625


b) Pre-drainage pumping (example shown is a deepwell system)

Figure 1: Examples of groundwater control by pumping (reproduced from Cashman and Preene, 2021, with permission)




626
627
628

- a) Groundwater exclusion using vertical barriers sealed into a low permeability stratum below the excavation



629
630
631


- b) Horizontal barrier elements of ground treatment used to exclude groundwater from a tunnel under construction



Overlapping discs to form base plug

632
633
634

- c) Vertical barriers used in combination with a low permeability base plug formed by ground treatment methods




635
 636
 637
 638
 639
 640
 641

d) Shaft construction by the wet caisson method, where water inside the flooded caisson provides a fluid counter pressure to balance groundwater inflows


Figure 2: Examples of groundwater control by exclusion (reproduced from Cashman and Preene, 2021, with permission)

642
643



644
645
646

a) Range of application of groundwater control pumping methods in granular soils (from Preene et al., 2016; reproduced courtesy of CIRIA: www.ciria.org)




647
648
649
650
651
652

b) Tentative economic ranges for groundwater exclusion methods in soils (from Preene et al., 2016; reproduced courtesy of CIRIA: www.ciria.org)


Figure 3: Guidance on the range of application of groundwater control methods

653



654
655
656
657
658

- a) High risk of dewatering-related settlement if groundwater level is lowered – soft silty clay will be underdrained and hence will consolidate



659
660
661
662
663
664
665
666

- b) Low risk of dewatering-related settlement if groundwater level is lowered – soft silty clay is above the natural groundwater level and will not be affected by groundwater lowering

Figure 4: Examples of the impact of hydrogeological setting on risk of settlement due to lowering of groundwater levels

667




Figure 5: Installation of in-tunnel wellpoints in a tunnel heading (constructed by SEM/SCL methods) using an electrically driven drilling rig (Image courtesy of WJ Group)

668

669


670



671
672
673
674
675

Figure 6: Plan view of Tideway project drive shaft and adit located 120 m distant to a public water supply well

676



677
678
679
680
681

Figure 7: Ground profile and plot of groundwater levels and dewatering system abstraction flow

682




Figure 8: Groundwater control for tunnels: surface dewatering compared with in-tunnel dewatering techniques

683

684


685
686



687
688
689
690
691
692

Figure 9: Compact ejector pumping station for use in shafts or tunnels with inclined ejector wells installed through a concrete secant pile wall to control external hydrostatic pressures and base seepage inflow (Image courtesy of WJ Group)

693




a) Cross section

694

695

696

697



b) Plan view

698

699

700


701

702

703

Figure 10: Layout for in-tunnel dewatering for a cross passage with a water bearing granular horizon below invert

704



705
706
707

Figure 11: Revised range of application of groundwater control pumping methods in granular soils (updated from guidance in CIRIA Report C750 (Preene et al, 2016))